

AD-A146 327

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
QUINSIGAMOND POND DAM..(U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV AUG 78


1/1

UNCLASSIFIED

F/G 13/13

NL

END
DATE
FILMED
10-84
DTIC



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A146 327

BLACKSTONE RIVER BASIN
WORCESTER, MASSACHUSETTS

QUINSIGAMOND POND DAM
MA 00139

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**

DTIC FILE COPY



DTIC
ELECTE
OCT 03 1984

E
X

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

This document has been approved
for public release and sale; its
distribution is unlimited.

AUGUST 1978

84 : 09 28 064

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER MA 00139	2. GOVT. ACCESSION NO. A146327	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Quinsigamond Pond Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE August 1978
		13. NUMBER OF PAGES 60
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		16a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Blackstone River Basin Worcester, Mass.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Quinsigamond Pond Dam is an earthfill dam with an arched, stone masonry spillway. The dam and spillway is about 240 feet long and 18 feet high. The dam is considered to be in fair condition. In addition, the dam has been classified in the "high" hazard category. Based on size and hazard classification, the test flood is $\frac{1}{2}$ the PMF. ↑		



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:

NEDED

JUN 18 1979

Honorable Edward J. King
Governor of the Commonwealth of
Massachusetts
State House
Boston, Massachusetts 02133

Dear Governor King:


I am forwarding to you a copy of the Quinsigamond Pond Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Environmental Quality Engineering, the cooperating agency for the Commonwealth of Massachusetts. In addition, a copy of the report has also been furnished the owner, Riley Stoker Company, P.O. Box 547, Worcester, Massachusetts 01613.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Quality Engineering for your cooperation in carrying out this program.

Sincerely yours,


JOHN P. CHANDLER
Colonel, Corps of Engineers
Division Engineer

Incl
As stated

QUINSIGAMOND POND DAM

MA 00139

BLACKSTONE RIVER BASIN
WORCESTER, MASSACHUSETTS

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION
PROGRAM

Accession For		
NTIS CRA&I	<input checked="" type="checkbox"/>	
DTIC TAB	<input checked="" type="checkbox"/>	
Unannounced	<input type="checkbox"/>	
Justification		
By		
Distribution/		
Availability Codes		
Small and/or		
Dist	Special	
A-1		



NATIONAL DAM INSPECTION
PROGRAM

PHASE I INSPECTION REPORT

BRIEF ASSESSMENT

Identification No.: MA00139

Name of Dam: Quinsigamond Pond

Town: Worcester

County and State: Worcester County, Massachusetts

Stream: Middle River, a tributary of the Blackstone
River

Date of Inspection: August 3, 1978

Quinsigamond Pond Dam is an earthfill dam with an arched, stone masonry spillway. The spillway comprises the major portion of the dam. An earlier dam was constructed at the site some time prior to 1833. The present spillway was built in 1891, and there were subsequent modifications to the embankment and outlets. The dam and spillway is about 240 feet long and 18 feet high. The spillway section, which is 155 feet long, has a cut-off wall of 4-inch sheeting that extends at least 10 feet into the embankment. There are two visible outlet gate structures in the south abutment area. One gate is inoperable and the other gate is reportedly still operable, although it has not been used in over 5 years.

Quinsigamond Pond Dam was neither designed nor constructed by current approved, state-of-the-art procedures. Based upon the visual inspection at the site and the limited engineering data available, there are areas of concern which must be corrected to assure the continued performance of this dam. Generally, the Quinsigamond Pond Dam is considered to be in fair condition. In addition, the dam has been classified in the "high" hazard category.


The following visible signs of distress indicate a potential hazard at the dam: heavy siltation upstream of the dam, resulting in the accumulation of weeds, brush and debris that seriously restricts spillway flow and reduces the storage capacity of the pond; the deteriorating condition of the flashboards; the growth of grass between the blocks of the face of the spillway; the missing gate stem at one outlet; trees growing on the embankment, and stonework missing from the north abutment of the spillway.

Hydraulic analyses indicate that the spillway can discharge a flow of 6,600 cfs at El 445.7, which is the low point of the dam. Based on size and hazard classifications in accordance with Corps guidelines, the test flood is one-half the maximum probable flood. The inflow test flood of 17,140 cfs, is adjusted for surcharge storage, resulting in an outflow of 17,075 cfs. This outflow will overtop the main dam by a maximum height of 3.1 feet. The spillway is inadequate since it can discharge only 38 percent of the test flood before the dam is overtopped. However, due to the regulating effect of the upstream flood control structure which was installed in 1959, it is unlikely that overtopping the dam is a serious hazard. However, it is recommended that a definite surveillance plan and warning system be developed for use during periods of unusually heavy rain or runoff, since overtopping could result in complete failure of the dam.

Further investigations to assess the adequacy of the dam are not considered necessary at this time. However, an analysis should be performed to determine the limits of dredging of soil upstream of the dam so that the stability and impermeability of the dam is unimpaired. For the present time, it is recommended that the Owner remove the remaining flashboards from the weir; dredge soil and vegetation from the area upstream of the spillway; repair the outlet works next to the south abutment of the spillway; clear trees and brush from the earth embankment; and replace the blocks missing from the wall at the north abutment. The Owner should also implement a systematic program of inspection and maintenance.

The recommendations and remedial measures described in Section 7 should be implemented by the Owner

within a period of one year after receipt of this Phase I Inspection Report. An alternative to these recommendations would be draining the pond and breaching or removing the dam. However, prior to breaching the dam all accumulated soil within the pond should be removed and disposed of offsite.



A handwritten signature of Edward M. Greco in cursive script.

Edward M. Greco, P.E.
Project Manager
Metcalf & Eddy, Inc.

Connecticut Registration
No. 08365

Approved by:

A handwritten signature of Stephen L. Bishop in cursive script.

Stephen L. Bishop, P.E.
Vice President
Metcalf & Eddy, Inc.

Massachusetts Registration
No. 19703



This Phase I Inspection Report on Quinsigamond Pond Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.



CHARLES G. TIERSCH, Chairman
Chief, Foundation and Materials Branch
Engineering Division




FRED J. RAVENS, Jr., Member
Chief, Design Branch
Engineering Division



SAUL COOPER, Member
Chief, Water Control Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in Recommended Guidelines for Safety Inspection of Dams, for a Phase I Investigation. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D. C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

	<u>Page</u>
BRIEF ASSESSMENT	
PREFACE	
OVERVIEW PHOTO	111
LOCATION MAP	iv
REPORT	
SECTION 1 - PROJECT INFORMATION	1
1.1 General	1
1.2 Description of Project	2
1.3 Pertinent Data	5
SECTION 2 - ENGINEERING DATA	10
2.1 General	10
2.2 Construction Records	11
2.3 Operation Records	11
2.4 Evaluation of Data	11
SECTION 3 - VISUAL INSPECTION	12
3.1 Findings	12
3.2 Evaluation	14
SECTION 4 - OPERATION PROCEDURES	15
4.1 Procedures	15
4.2 Maintenance of Dam	15
4.3 Maintenance of Operating Facilities	15
4.4 Description of Any Warning System in Effect	15
4.5 Evaluation	15
SECTION 5 - HYDRAULIC/HYDROLOGIC	16
5.1 Evaluation of Features	16

TABLE OF CONTENTS
(Continued)


	<u>Page</u>
SECTION 6 - STRUCTURAL STABILITY	19
6.1 Evaluation of Structural Stability	19
SECTION 7 - ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES	21
7.1 Dam Assessment	21
7.2 Recommendations	22
7.3 Remedial Measures	22
APPENDIXES	
APPENDIX A - PERIODIC INSPECTION CHECKLIST	
APPENDIX B - PLAN OF DAM AND PREVIOUS INSPECTION REPORTS	
APPENDIX C - PHOTOGRAPHS	
APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS	
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	

OVERVIEW
QUINSIGAMOND POND
WORCESTER, MASSACHUSETTS



VIEW FROM SOUTH ABUTMENT

Location and Direction of Photographs
Shown on Figure in Appendix B



LOCATION MAP - QUINSIGAMOND POND DAM

NATIONAL DAM INSPECTION
PROGRAM

PHASE I INSPECTION REPORT

QUINSIGAMOND POND

SECTION 1

PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Metcalf & Eddy, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Massachusetts. Authorization and notice to proceed was issued to Metcalf & Eddy, Inc. under a letter of May 3, 1978, from Ralph T. Garver, Colonel, Corps of Engineers. Contract No. DACW 33-78-C-0306 has been assigned by the Corps of Engineers for this work.

b. Purpose:

- (1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.
- (2) Encourage and assist the States to initiate quickly effective dam safety programs for non-Federal dams.
- (3) Update, verify and complete the National Inventory of Dams.

1.2 Description of Project

- a. Location. The dam is located on Middle River, a tributary of the Blackstone River, in the City of Worcester, Worcester County, Massachusetts (see Location Map, and Watershed Plan, Figure D-1).
- b. Description of Dam and Appurtenances. Quinsigamond Pond Dam consists primarily of an arched, mortared stone masonry spillway with an earthfill embankment at the southern end. The dam and spillway are about 240 feet long and the dam has a maximum height of 18 feet. The spillway is 155 feet long and constructed of mortared stone blocks with a battered downstream face and a stepped upstream face (see Figure B-3). Drawings indicate that there is a cutoff of wood sheeting beneath the spillway wall 3 feet from the upstream face. This sheeting is shown to extend laterally at least 10 feet beyond the ends of the spillway. The crest of the dam is comprised of granite cap blocks 5.4 feet wide, and varies from El 440.8 to 441.2. Flashboards 1.8 feet high are mounted with steel pins on the northern 90 feet of the crest. The flashboards have collapsed along the southern portion of the crest. The top of the flashboards varies from El 442.6 to 443.0. Sidewalls of the spillway are constructed of mortared stone and are 4.7 feet (south end) to 4.9 feet (north end) above the crest. Drawings indicate that the toe of the dam has been protected by a 12-foot-wide apron, constructed of concrete and covered with wood planking. At the downstream edge of this apron is another cutoff of wood sheeting. The spillway discharges into a recessed channel 165 feet wide with vertical, mortared stone walls 12.5 feet high.

The crest of the earth fill embankment at the south end of the spillway is irregularly

shaped and is at an approximate elevation of 445.5. The upstream face of the dam is a vertical, mortared stone wall. The downstream face has been filled in approximately level with the crest to construct a road and railroad tracks. A locked chain-link fence is along the crest and Greenwood Street to prevent access to the outlet structures.

There are two known outlet structures for the dam. One, located at the south abutment of the spillway, is a 6-foot-long, mortared stone sluiceway controlled by a 6-foot by 5-foot slide gate. This gate is operated by a rack and pinion mechanism mounted on grating. The wooden portion of the gate stem is missing and the gate is inoperable. The invert elevation of this outlet is 433.4, and it discharges at the downstream face of the spillway abutment.

A second outlet is located 66 feet south of the spillway, near the abutment of the dam. It is a concrete sluiceway controlled by a 4-foot by 3-foot slide gate. The gate, which is reportedly operable, can be regulated by a rack and pinion mechanism mounted on the headwall of the conduit. The outlet was used to provide water to a U. S. Steel factory. The length and discharge point of this outlet are unknown. There is also evidence of two other abandoned outlets within the pond. There is no information available on these outlets.

- c. Size Classification. Quinsigamond Pond Dam is classified in the "small" category since it has a maximum height of 18 feet and a maximum storage capacity of 180 acre-feet.
- d. Hazard Classification. Downstream of the dam is a heavily industrialized area, including several large factories and bridges for a railroad, Greenwood Street, and Millbury Street. In the event of overtopping and complete failure of the dam, more than a few lives could be lost and extensive property damage could occur. Accordingly the dam has been classified in the "high" hazard category.

- e. Ownership. The dam is located on property owned by Riley Stoker Company, P. O. Box 547, Worcester, Massachusetts 01613. Mr. Tom Kennedy (617-852-7100 ext. 234) granted permission to enter the property and inspect the dam. Prior to February 1973 the dam and water rights were owned by U. S. Steel Corporation.
- f. Operators. There are no known operators of this dam. The outlet structures are inside a 5-foot-high, locked chain-link fence, and the Riley Stoker Company has the key.
- g. Purpose of Dam. Until 1973, the dam provided water for industrial purposes at a steel mill. It used to be called "South Works Pond" and, in 1947, supplied 18.7 million gallons of water per day to the American Steel and Wire Company (see listing of ponds in Figure D-1). The dam has not been used since 1973, and now serves indirectly for flood control.
- h. Design and Construction History. An earlier dam was constructed at the site of the present dam some time prior to 1833. There are no drawings available that show its construction. The existing spillway section of the dam was built about 1891 (see Figure B-3). At that time, the dam was owned by the Washburn & Moen Manufacturing Company. Some time between 1891 and 1947, the dam became the property of American Steel & Wire Company, a subsidiary of U. S. Steel Corporation, which owned the dam until 1973.

Previous inspection reports indicate that the flashboards were in place and the outlet gates were in use as early as 1925.

In 1936, the dam was repaired and the earth embankment and a cut off of wood sheeting were extended 36 feet (see note on inspection listing, page B-4). In 1945, an inspection report stated that a "new concrete headwork" had been constructed for the outlet gate near Greenwood Street.

1. Normal Operating Procedure. There are no operating procedures at the dam. There are two known outlet structures controlled by slide gates located near the south end of the dam. The outlet next to the spillway is missing the wooden portion of the gate stem and is inoperable. The outlet next to Greenwood Street is reported to be operable, but has not been opened in over five years. There is also evidence of two other abandoned outlets within the pond. There is no information available on these outlets.

The spillway for Quinsigamond Pond Dam is ungated. Sections of the existing flashboards have collapsed and a major portion of the pond near the spillway is filled with silt. Normal flows are restricted to about 40 percent of the length of the crest.

1.3 Pertinent Data

- a. Drainage Area. The approximately 40,300 acre (63 square mile) drainage area includes the basins of Ramshorn Brook, Dark Brook, Tatnuck Brook, Kettle Brook, and Middle River. About 25 dams are located upstream of Quinsigamond Pond, and seven of these reservoirs are used for water supply. Runoff from approximately 11.3 square miles of the area directly tributary to Quinsigamond Pond is diverted by the City of Worcester drainage system (Mill Brook Storm Drain) and discharged downstream of the dam into the Blackstone River. This results in a drainage area of 51.7 square miles directly tributary to the pond. A diversion tunnel is also located on Kettle Brook and conducts flood water downstream of Quinsigamond Pond Dam.

The drainage area is about 50 percent rural and 50 percent urban. Rural areas are sparsely populated, generally wooded, and have gentle to steep slopes. Urban areas are moderate to densely populated, with few wooded areas, and have flat to moderate slopes.

Discharge from Quinsigamond Pond Dam is to the Blackstone River, located directly downstream. The downstream area is a heavily developed, industrial and commercial section of Worcester.

- b. Discharge. Normal discharge is over the spillway which is ungated. The spillway weir is about 155 feet long, and the crest elevation varies from 440.8 to 441.2. Wooden flashboards 1.8 feet high are mounted on the northern 90 feet of the crest. Water drops about 8 feet vertically into a downstream channel which is 165 feet wide with vertical stone sidewalls 12.5 feet high. Three granite block piers that support a railroad bridge are located 20 feet downstream of the dam. Two concrete piers that support the Greenwood Street bridge are located 115 feet downstream of the dam. The channel has a downstream slope of less than 1 percent and narrows to 100 feet wide at 500 feet below the dam. At that point, the channel makes a 90 degree turn to the right and continues in a southeasterly direction.

The spillway can discharge an estimated 6,600 cfs at El 445.7 which is the low point of the dam. The inflow test flood, which has been adjusted for water diverted to the Worcester Diversion Tunnel and Mill Brook Storm Drain, is 17,140 cfs and will overtop the dam by a maximum of 3.1 feet.

The maximum flood level at the dam is unknown. County personnel recall that the dam was not overtopped in 1936 or 1955; however, a 1936 flood level of El 447 is shown on the list of inspections (see page B-4). This is 1.5 feet above the lowest point on the crest of the dam.

- c. Elevation [feet above Mean Sea Level (MSL)]. A benchmark at El 441.0 was established at the spillway crest. This elevation was estimated from a U.S.G.S. topographic map.

- (1) Top dam: 445.7 to 446.2
- (2) Test flood pool: 448.8
- (3) Design surcharge (original design):
unknown
- (4) Full flood control pool: Not Applicable
(N/A)

- (5) Recreation pool: 441.0
- (6) Spillway crest (ungated): 441.0
- (7) Upstream portal invert diversion tunnel (Worcester Diversion): 487.0 (upstream diversion spillway crest elevation: 492)
- (8) Stream bed at centerline of dam: 433.3 at top of downstream apron
- (9) Maximum tailwater: 441.7 at test flood

d. Reservoir

- (1) Length of maximum pool: 4,500 feet
- (2) Length of recreation pool: 4,500 feet
- (3) Length of flood control pool: N/A

e. Storage (acre-feet)

- (1) Test flood surcharge: 80 at El 445.7
- (2) Top of dam: 180
- (3) Flood control pool: N/A
- (4) Recreation pool: 100 (Approximate)
- (5) Spillway crest: 100

f. Reservoir Surface (acres)

- *(1) Top dam: 17
- *(2) Test flood pool: 17
- (3) Flood-control pool: N/A
- (4) Recreation pool: 17
- (5) Spillway crest: 17

*Based on the assumption that the surface area will not increase significantly with changes in reservoir elevation from 441.0 to 445.7.

g. Dam

- (1) Type: earthfill
- (2) Length: 240 feet
- (3) Height: 18 feet
- (4) Top width (earth embankment at south end of spillway): varies from 10 to 35 feet
- (5) Side slopes: upstream - vertical, downstream - filled to street grade
- (6) Zoning: Unknown
- (7) Impervious core: 4-inch timber sheeting
- (8) Cutoff: 4-inch timber sheeting in concrete
- (9) Grout curtain: Unknown

1. Spillway

- (1) Type: Narrow crest
- (2) Length of weir: 155 feet
- (3) Crest elevation: 441.0 MSL (assumed benchmark)
- (4) Gates: None
- (5) Upstream channel: stone masonry side-walls along pond
- (6) Downstream channel: 12-foot-wide concrete apron at downstream toe. Leads to 165-foot-wide channel with vertical masonry walls 12.5 feet high.
- (7) General: Downstream railroad bridge 25 feet from dam - then culvert under Greenwood Street, to stream channel with mortared masonry sidewalls. Channel takes 90 degree bend to southeast about 500 feet from dam.

- j. Regulating Outlets. There are two known regulating outlets at the dam. One is located at the south abutment of the spillway. It is a 6 foot long, mortared stone sluiceway which is controlled by a 6- by 5-foot slide gate. This outlet is missing the wooden portion of the gate stem and is inoperable. The second outlet is near the abutment of the dam, and closer to Greenwood Street. It is a concrete sluiceway controlled by a 4-foot by 3-foot slide gate. The gate, although reportedly still operable, has not been used in over 5 years. There is also evidence of two other abandoned outlets within the pond. There is no information available on these outlets.

SECTION 2
ENGINEERING DATA

- 2.1 General. The only plans, specifications, or computations available from the Owner or State or County offices relative to the design, construction or repair of this dam is a "Plan of Dam Across the Blackstone River" filed in July 28, 1891. This plan shows details of the spillway weir, the concrete apron at the downstream toe, and two cutoff walls. A copy of this plan is included in Figure B-3 in Appendix B.

Supplementary information for the hydraulic-hydrologic evaluation for the dam was provided by U. S. Army Corps of Engineers "Design Memorandum No. 1" dated August 1975 for the Worcester Diversion. Three plans for this tunnel and the control dam were provided by the Corps, but were not included in this report. The only other data available for this evaluation were visual observations during inspection, review of previous inspection reports, and conversations with the Owner and with personnel from the State, County, and City agencies.

We acknowledge the assistance and cooperation of personnel of the Massachusetts Department of Public Works: Messrs. Willis Regan and Raymond Rochford, and of the Massachusetts Department of Environmental Quality Engineering, Division of Waterways: Messrs. John J. Hannon and Joseph Iagallo.

Also, we acknowledge the cooperation and assistance of personnel from the Worcester County Engineer's Office: Messrs. John O'Toole, Joseph Brasauskas, and Mr. Wallace Lindquist - recently retired from county service.

In addition, we thank Mr. Thomas M. Kennedy of the Riley Stoker Corporation, Owner of the dam, who gave permission to inspect the dam and provided access to the outlet structures.

- 2.2 Construction Records. The only construction record is the 1891 Plan referred to in section 2.1 and included in Appendix B. There are no as-built drawings for the dam, spillway and outlet structures.
- 2.3 Operating Records. No operating records are available, and there is no daily record kept of the elevation of the pool or rainfall at the dam site.
- 2.4 Evaluation.
- a. Availability. Due to the age of this dam, there is limited engineering data available.
 - b. Adequacy. The lack of in-depth engineering data did not allow for a definitive review. Therefore the adequacy of this dam could not be assessed from the standpoint of reviewing design and construction data but is based primarily on visual inspection, past performance history, and sound engineering judgment.
 - c. Validity. The limited engineering data available is considered valid.

SECTION 3
VISUAL INSPECTION

3.1 Findings

- a. General. The Phase I inspection of the dam at Quinsigamond Pond was performed on August 3, 1978. A copy of the inspection checklist is included in Appendix A. Periodic inspections of this dam by others have been made since 1925. A partial listing of these inspections is in Appendix B. An inspection was made in 1973 by personnel of the Massachusetts Department of Public Works. Copies of those reports are also in Appendix B.
- b. Dam. The dam consists of a stone masonry spillway with an earthfill embankment at the southern end. The earthfill embankment includes the outlet structures. The embankment is generally in fair condition. The downstream slope has been filled in to street grade. The upstream face is a vertical cut stone wall that appears to be in fair to good condition. The crest of the embankment is covered with grass and brush, and a few stones. A large tree is growing on the south abutment, outside the chain-link fence surrounding the outlet structures. The only visible concrete structure is on the embankment in the area of the outlets.

At the north abutment of the dam, stone blocks are missing from the top of the wall. Surface runoff flows into the pond immediately upstream of the weir.
- c. Appurtenant Structures. The spillway is an arched, mortared stone structure located at the north end of the dam. Flashboards are mounted on the northern 90 feet of the crest. Upstream of the spillway there is a major accumulation of soil, vegetation, and debris. The upstream face of the spillway, which was originally constructed with stepped stone blocks, is now entirely silted in almost to the crest. The silt supports vegetation and seriously impedes the flow. This problem is particularly acute in

the area directly upstream of the section of the spillway which has flashboards. The deposition of silt and dense growth of weeds have built up the pond bed above the crest of the weir.

The flashboards have collapsed from the southern 65 feet of the crest of the spillway, and water is flowing over the weir. A broken piece of flashboard suspended by one pin remains in this section.

The stonework on the spillway is in good condition, although grass is growing between the blocks on the face of the weir, and on the sidewalls.

Two outlets which are located at the south abutment of the dam are surrounded by a locked chain-link fence. The channel nearest the spillway is in poor condition. The approach channel and intake are submerged, and the stone masonry sidewalls and concrete headwall of the outlet structure appear to be in fair condition. The wooden parts of the gate stem are missing, however, making the gate inoperable. There is a thick growth of shrubbery on top of the outlet structure. The outlet channel which connects with the spillway channel appears to be clear of debris.

The second outlet is closer to Greenwood Street, and was used to provide water to the former steel mill. The concrete of the sluiceway is in fair condition, with minor spalling and erosion evident, but no staining. The Owner reports that the gate is still operable. The downstream outlet channel is not visible. There is also evidence of two other abandoned outlets within the pond.

- d. Reservoir Area. Quinsigamond Pond is bounded on the west by Middle River Park, and beyond that by Holy Cross College on College Hill. The rest of the pond area is surrounded by highly urbanized sections of Worcester, including a number of factories downstream. At the upstream end of the pond, the Middle River flows under I-290 before discharging into Quinsigamond Pond.

- e. Downstream Channel. The discharge from the spillway flows in the stream channel under the railroad bridge and Greenwood Street, and into the Blackstone River. The channel has vertical mortared stone sidewalls for at least 500 feet below the dam, where it makes a 90 degree bend to the southeast.

3.2 Evaluation. The above findings indicate that there are areas of concern at the dam which require attention. It is evident that the dam is not adequately maintained and that deterioration will continue unless action is taken. Recommended measures to improve these conditions are stated in Section 7.

SECTION 4

OPERATING PROCEDURES

- 4.1 Procedures. There are no operating procedures at Quinsigamond Pond Dam.
- 4.2 Maintenance of the Dam. The dam is not adequately maintained. Silt, debris and vegetation have been allowed to accumulate in the pond and approach to the spillway. This condition has been of major concern as noted on previous inspection reports since 1938. Also, the growth of trees and brush on the embankment and between the stone blocks of the upstream walls has not been controlled.
- 4.3 Maintenance of Operating Facilities. One of the outlets at the south end of the spillway is inoperable. The slide gates are closed and cannot be opened with the existing mechanism. It is reported that the other outlet is operable.
- 4.4 Description of Any Warning Systems in Effect. There are no warning systems in effect at this dam.
- 4.5 Evaluation. There are no operational, maintenance, or warning systems in effect at Quinsigamond Pond Dam. This is extremely undesirable considering the fact that it is in the "high" hazard category. A program of operation and maintenance for this dam should be implemented as recommended in Section 7.

SECTION 5

HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

- a. Design Data. The Probable Maximum Flood (PMF) rate was determined to be 850 cfs per square mile. This rate was determined based upon the U. S. Army Corps of Engineers' guide curves for Maximum Probable Flood Peak Flow Rates, dated December 1977, modified to show the calculated peak flow rate for Leesville Pond (MA 00141) and extrapolated to different tributary areas.

The total drainage area to Quinsigamond Pond Dam was calculated to be approximately 63 square miles, and includes the tributary drainage areas for Leesville Pond (32.1) Coes Reservoir (10.9), Curtis Ponds (1.2), and the 18.7 square miles of area contributing directly to Quinsigamond and comprising most of urban Worcester. The Mill Brook storm drain, which discharges just downstream of Quinsigamond Pond, collects drainage from 11.3 square miles of the City of Worcester. Subtracting this diverted flow from 63 square miles results in a directly tributary drainage area for Quinsigamond Pond of 51.7 square miles.

Applying one-half the PMF rate to the 51.7 square miles and using an appropriate reduction factor for areas exceeding 10 square miles results in a calculated inflow test flood of 20,475 cfs. The Worcester Diversion just upstream of Leesville Pond can divert 6,000 cfs directly to the Blackstone River downstream of Quinsigamond Dam. Therefore, the final adjusted inflow test flood is anticipated to be 14,475 cfs.

An alternative method for verification of the calculated inflow test flood was to use the peak outflows of both Coes and Leesville Reservoirs (calculated in previous Phase I Inspection Reports MA 00120 and 00141) plus the total flow from the remaining 8.7 square miles of drainage to Quinsigamond. This method gives an inflow test flood of 19,800 cfs.

The average of the two flow rates was calculated to be 17,140 cfs (332 cfs per square mile) and was used as the inflow test flood for this analysis. By adjusting the inflow test flood for surcharge storage, the maximum discharge rate was established as 17,075 cfs, with the water surface at El 448.8. Flow over the crest of the embankment is predicted to be 1,020 cfs while flow over the main spillway would be 16,055 cfs. The maximum head on the dam would be 3.1 feet, with a discharge of 14 cfs per foot of width. The depth of water over the dam at critical flow would be 0.76 feet with a velocity of 5.0 feet per second.

Hydraulic analyses indicate that the spillway can discharge flows of 6,600 cfs with a water surface at El 445.7 which is a low point of the dam.

- b. Experience Data. Hydraulic records are not available. A review of past records and discussions with County personnel indicated that the dam was not overtopped during the 1938 or the 1955 floods; however, the 1936 flood reached El 447 as indicated on the list of partial inspections (see page B-4). This is 1.5 feet above the low point on the crest of the dam but below the top of the railroad rails just downstream of the dam.
- c. Visual Observations. Discharge from Quinsigamond Pond is over an arched, masonry spillway about 155 feet long with an 8 foot vertical downstream face. Water flows beneath a railroad trestle bridge about 20 feet downstream and then through a more constricted opening under Greenwood Street. Two unknown outlet structures are located at the southerly end of the dam. There is also evidence of two other abandoned outlets within the pond.

Eighteen-inch-high flashboards are present along the spillway although in one section the flashboard has partially fallen off. Immediately upstream of the spillway, at the north abutment, the approach is filled with silt and cluttered with debris.

- d. Overtopping Potential. Overtopping of the dam is expected under the inflow test flood of 17,140 cfs. Failure of the dam during peak test flood outflow would cause only a small increase in discharge. This is due to the fact that the spillway would already be discharging at a high rate under the test flood and would be submerged by the discharge tailwater.

SECTION 6

STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

- a. Visual Observations. The evaluation of the structural stability of Quinsigamond Pond Dam is based on the visual inspection of August 3, 1978. Based on the visual observations as detailed in Section 3, Visual Inspection, Quinsigamond Pond Dam does not appear to be unstable. However, in the event the soil is removed upstream of the spillway, an unstable condition could result. An analysis to determine the limits of dredging should be performed so that the stability and impermeability of the dam is unimpaired.
- b. Design and Construction Data. The 1891 drawing showing the details of the spillway section is the only available information relative to the design and construction of the dam. Information on the type, shear strength, and permeability of the soil and/or rock materials of the dam embankment does not appear to exist.

The cutoff for the spillway is shown in Figure B-3 as 4-inch sheeting in concrete. Protection of the downstream toe of the spillway is provided by a concrete slab and wood plank-ing.

- c. Operating Records. There is no evidence that instrumentation of any type was ever installed in Quinsigamond Pond Dam. The performance of this dam under prior loading can only be inferred by previous records and physical evidence at the site.
- d. Post-Construction Changes. There are no as-built drawings for the dam. As discussed in Section 1.2.h, previous inspection reports indicate that in 1936 a cutoff of wood sheeting and 36 feet of earth embankment were constructed. In 1945, a "new concrete headwork" had been constructed for the outlet gate near Greenwood Street.

- e. Seismic Stability. The dam is located in Seismic Zone No. 2 and in accordance with Phase I "Recommended Guidelines" does not warrant seismic analyses.

SECTION 7

ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1 Dam Assessment

- a. Condition. Quinsigamond Pond Dam was neither designed nor constructed according to the current approved state-of-the-art procedures. Based upon the visual inspection at the site, the lack of engineering data, and limited evidence of operational or maintenance procedures; there are areas of concern which must be corrected to assure the continued performance of this dam. Generally, the dam is considered to be in fair condition. One of the most serious signs of distress observed at the site was extensive deposition of silt upstream of the spillway. On the northern half of the weir, where the flashboards are in place, soil, weeds, and brush have accumulated above the crest of the spillway. This condition restricts flow over about 90 feet of the spillway. In addition, silt which has been deposited farther upstream has significantly reduced the storage capacity of the pond. The flashboards on the southern portion of the weir have been washed away, and normal flow is over that section of the spillway. That area is also silted up on the upstream face almost to the crest.

Other signs of distress are: the growth of grass between stone blocks on the face of the spillway, the missing gate stem on the outlet at the south end of the spillway, trees growing on the earth embankment near the outlet structures, and stonework missing from the north abutment of the spillway.

Hydraulic analyses indicate that the existing spillway can discharge a flow of 6,600 cfs at El 445.7 which is the low point on the crest of the dam. An inflow test flood of 17,140 cfs will overtop the dam by a maximum of 3.1 feet.

Previous records indicate the dam may have been overtopped by 1.5 feet during the 1936 storm. However, due to the present regulating effects of the upstream flood control structure which was installed in 1959, it is unlikely that this is a serious hazard.

- b. Adequacy of Information. The lack of in-depth engineering data did not allow for a definitive review. Therefore the adequacy of this dam could not be assessed from the standpoint of reviewing design and construction data, but is based primarily on visual inspection, past performance history and sound engineering judgment.
- c. Urgency. The recommendations and remedial measures outlined below should be implemented by the Owner within one year after receipt of this Phase I Inspection Report.
- d. Need for Additional Information. Additional investigations to further assess the adequacy of this dam are not required at the present time except in regard to the limits of dredging to remove accumulated soil. Remedial measures for repairing and maintaining the dam are stated below in Section 7.3 Remedial Measures.

- 7.2 Recommendations. As a result of the visual inspection and a review of available data, further investigations to assess the adequacy of the dam are not considered necessary at this time except in regard to proposed dredging. Prior to any dredging it is recommended that the Owner employ a qualified consultant to determine the limits of dredging so that the stability and impermeability of the dam is unimpaired. Also, future changes within the watershed or to the dam and/or spillway may necessitate further investigations.

The recommendations on repair and maintenance procedures are stated below in Section 7.3.

7.3 Remedial Measures

- a. Alternatives. An alternative to recommendations above and the maintenance procedures

itemized below would be to drain the pond and breach or remove the dam. However, prior to breaching the dam all accumulated soil within the pond should be removed and disposed of off-site.

b. Operating and Maintenance Procedures. The dam and appurtenant structures are not adequately maintained. It is recommended that the Owner accomplish the following:

- (1) remove the flashboards from the northern 90 feet of the weir of the spillway
- (2) dredge soil and vegetation from the area upstream of the spillway. The limits of dredging should be based on an analysis as recommended above
- (3) repair the gate stem on the outlet works next to the south abutment of the spillway and determine that the gate operates properly
- (4) clear trees and brush from the earth embankment at the south end of the dam near the outlet structures
- (5) repair stone blocks missing from the top of the wall just upstream of the north abutment of the dam
- (6) institute a definite plan for surveillance and a warning system during periods of unusually heavy rains and/or runoff; this should be coordinated with the operators of upstream reservoirs
- (7) implement a systematic program of maintenance inspections. As a minimum, the inspection program should consist of a monthly inspection of the dam and appurtenances supplemented by additional inspections during and after severe storms. All repairs and maintenance should be undertaken in accordance with all applicable State regulations.

- (8) periodic technical inspections of this dam should be continued on a bi-annual frequency.

APPENDIX A
PERIODIC INSPECTION CHECK LIST

PERIODIC INSPECTION

PARTY ORGANIZATION

PROJECT Quinsigamond Pond

DATE August 3, 1978

TIME 8:00 AM - 1:00 PM

WEATHER Sunny - 75°F

W.S. ELEV. 441.1 U.S. 434.5 D.N.S.

*assumed benchmark EI 441 at
spillway crest from USGS topo quad

PARTY:

- | | |
|-------------------------|-----------|
| 1. <u>Lyle Branagan</u> | 6. _____ |
| 2. <u>David Cole</u> | 7. _____ |
| 3. <u>Leu Taverna</u> | 8. _____ |
| 4. <u>Ed Greco</u> | 9. _____ |
| 5. _____ | 10. _____ |

PROJECT FEATURE

INSPECTED BY

REMARKS

- | | |
|----------------------------|-----------------------------------|
| 1. <u>dam and spillway</u> | <u>Lyle Branagan and Ed Greco</u> |
| 2. <u>outlets</u> | <u>Lyle Branagan</u> |
| 3. _____ | _____ |
| 4. _____ | _____ |
| 5. _____ | _____ |
| 6. _____ | _____ |
| 7. _____ | _____ |
| 8. _____ | _____ |
| 9. _____ | _____ |
| 10. _____ | _____ |

PERIODIC INSPECTION CHECK LIST

PROJECT Quinsigamond Pond Dam DATE August 3, 1978
 PROJECT FEATURE dam embankment NAME Lyle Branagan
 DISCIPLINE geotechnical NAME Ed Greco

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	<i>varies from 445.5 to 446.2</i>
Current Pool Elevation	<i>441.1</i>
Maximum Impoundment to Date	<i>unknown</i>
Surface Cracks	<i>none visible</i>
Pavement Condition	<i>not applicable</i>
Movement or Settlement of Crest	<i>minor irregularities</i>
Lateral Movement	<i>none visible</i>
Vertical Alignment	<i>relatively flat</i>
Horizontal Alignment	<i>relatively straight</i>
Condition at Abutment and at Concrete Structures	<i>fair to good</i>
Indications of Movement of Structural Items on Slopes	<i>none visible</i>
Trespassing on Slopes	<i>upstream face heavily silted</i>
Sloughing or Erosion of Slopes or Abutments	<i>none visible</i>
Rock Slope Protection - Riprap Failures	<i>none visible</i>
Unusual Movement or Cracking at or near Toes	<i>none visible</i>
Unusual Embankment or Downstream Seepage	<i>minor seepage</i>
Piping or Boils	<i>none visible</i>
Foundation Drainage Features	<i>none visible</i>
Toe Drains	<i>none visible</i>
Instrumentation System	<i>none visible</i>

PERIODIC INSPECTION CHECK LIST

PROJECT Quinsigamond Pond Dam DATE August 3, 1978
 PROJECT FEATURE Spillway NAME Lyle Branagan
 DISCIPLINE geotechnical NAME Ed Greco

AREA EVALUATED	CONDITION
OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS	
a. Approach Channel	same as river channel
General Condition	severe siltation
Loose Rock Overhanging Channel	none
Trees Overhanging Channel	small trees + brush
Floor of Approach Channel	natural stream bed
b. Weir and Training Walls	fair to good - stone masonry
General Condition of Concrete	not applicable
Rust or Staining	not applicable
Spalling	not applicable
Any Visible Reinforcing	not applicable
Any Seepage or Efflorescence	minor seepage
Drain Holes	not applicable
c. Discharge Channel	under RR bridge + Greenwood Street
General Condition	fair to good with some debris
Loose Rock Overhanging Channel	no
Trees Overhanging Channel	small trees
Floor of Channel	natural with concrete + wood scour protection
Other Obstructions	two adjacent bridges

PERIODIC INSPECTION CHECK LIST

PROJECT Quinsigamond Pond Dam DATE August 3, 1978
 PROJECT FEATURE outlet structures NAME Lyle Branagan
 DISCIPLINE geotechnical NAME Ed Greco

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
a. Approach Channel	<i>Same as river channel</i>
Slope Conditions	<i>vertical masonry wall</i>
Bottom Conditions	<i>natural channel</i>
Rock Slides or Falls	<i>none</i>
Log Boom	<i>not applicable</i>
Debris	<i>minor</i>
Condition of Concrete Lining	<i>not applicable</i>
Drains or Weep Holes	<i>not applicable</i>
b. Intake Structure	<i>two inlets</i>
Condition of Concrete	<i>fair to good</i>
Stop Logs and Slots	<i>no logs- slots in concrete</i>

PERIODIC INSPECTION CHECK LIST

PROJECT Quinsigamond Pond Dam DATE August 3, 1978
 PROJECT FEATURE outlet structures NAME Lyle Branagan
 DISCIPLINE geotechnical NAME Ed Greco

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>	
General Condition of Concrete	<i>fair to good</i>
Rust or Staining on Concrete	<i>none</i>
Spalling	<i>minor</i>
Erosion or Cavitation	<i>minor</i>
Cracking	<i>none visible</i>
Alignment of Monoliths	<i>not applicable</i>
Alignment of Joints	<i>fair to good</i>
Numbering of Monoliths	<i>not applicable</i>

discharge channels:

outlet next to spillway - same channel as spillway


outlet next to Greenwood St - discharge off site

APPENDIX B

	<u>Page</u>
Figure B-1, Plan of Dam	B-1
Figure B-2, Sections	B-2
Figure B-3, Plan of Dam filed July 1891	in pocket
Previous Inspections (partial listing)	B-4
Previous Inspection Report by Massachusetts Department of Public Works, February 1973	B-6

MIDDLE RIVER

NS 471.1



Notes:

1. Information shown based on field survey of August 3, 1978 by Metcalf + Eddy, Inc.
2. Elevations shown based on assumed benchmark on spillway crest, El 441.0 (MSL)
3. * denotes marsh area
4. #2 shows direction of view of photographs
5. See Figure B-2 for sections

Metcalf & Eddy, Inc.




FIGURE B-1 PLAN OF DAM










FIGURE B-2 SECTIONS



1



PLAN



Detail of Copeing


SCALE 1" = 1'






PLAN

(4)




HOR. SCALE 1" = 8 FT.


Ver. " " 2 "




(6)



SCALE 1" = 8 FT.
" " 2 "



6



Section of Dam

Water line

12'

6 x 8

10 x 10

10 x 10

Concrete

4" Sheeting

Scale: 1/2" = 1'

PLAN

SCALE

SCALE 1" = 8 FT.

RAD 380.72

J.W. Ellis
WOONSOCKET

WORCESTER COUNTY COMMISSION
WORCESTER COUNTY ENGINEERING

PLAN OF
DAM

ACROSS THE BLACKSTONE RIVER
WORCESTER, MASS.

FOR THE WASHBURN & MOEN

AS FILED AND APPROVED

COUNTY COMMISSION

JULY 28, 1891

JUNE MEETING DOCUMENT

SCALES AS NOTED

TRACED BY: *J. W. Ellis* 3-4-36

TRACING CHECKED BY: *P. J. Marden* 6-36

DA

P. J. Marden

COUNTY

Attest W. Ellis

FT.

RAD 280.72

J.W. Ellis C.E.

WOONSOCKET R.I.

WORCESTER COUNTY COMMISSIONERS
WORCESTER COUNTY ENGINEERING DEPARTMENT

PLAN OF
DAM

ACROSS THE BLACKSTONE RIVER
WORCESTER, MASS.

FOR THE WASHBURN & MOEN MFG. CO.

AS FILED AND APPROVED BY THE

COUNTY COMMISSIONERS

JULY 28, 1891

JUNE MEETING DOCKET 122

SCALES AS NOTED

TRACED BY: *J. W. Ellis 3-4-36*

TRACING CHECKED BY: *J. W. Ellis 3-4-36*

DAM NO. 61-01

L. O. Marden

COUNTY ENGINEER

Attest William C. Bowen
Clerk

TOWN OR CITY	DECREE NO.	PLAN NO.	DAM NO.
Warcester	122		348
LOCATION	South Works- Millbury St., Quinsigamond Pond.		
DESCRIPTION OF DAM	Earth. Stone faced spillways.		
Type			
Length	90'		
Height	5'5"		
Thickness top	10'0"		
" bottom	12'1"		
Downstream Slope			
Upstream			
Length of Spillway	El. Top of Weir 437.8 125' 152'		
Size of Gates	3x3		
Location of Gates	So. End Spillway		
Flashboards used			
"Width Flashboards or Gates			
Dam designed by	J. W. Ellis.		
" constructed by			
Year constructed	1906		
GENERAL REMARKS	Owned by Am. Steel & Wire Co. Vol. 29 - P. 30. July 29, 1891, June 1894. Inspected Oct. 5, 1925. L.A.M. a.k. Plan - Dams C.C. Office Inspected: Oct. 29, 1928 - L.O.M. OK. " : Sept. 29, 1932 " " " : Mar. 1, 1933 " " " : Nov. 18, 1938 " " " : Dec. 1a 1940. " "		
DESCRIPTION OF RESERVOIR & WATERSHED			
Name of Main Stream	Blackstone River.		
" " any other Streams			
Length of Watershed			
Width "			
Is Watershed Cultivated			
Percent In Forests			
Steepness of Slope			
Kind of Soil			
No. of Acres in Watershed			
" " " Reservoir			
Length of Reservoir			
Width "			
Max Flow Cu. Ft. per Sec.			
Head or Flashboards-Low Water			
" " " High "			
GENERAL REMARKS	New Plans & Specs approved 9-15-36 by C.C. See plan in Commissioners Office Docket #122. Meeting June 1891. Filed July 29, 1891 Traced by: L.C. Farrar, March 4, 1936. Checked by: L. Q. Marden " 6 " Attested by: William C. Bowen C. of C. J. W. Ellis, C. E. - Woonsocket, R.I. 1936 Flood 447.0		

PREVIOUS INSPECTIONS (PARTIAL LISTING)

**COPY OF INSPECTION CARD ON FILE AT THE MASSACHUSETTS
DEPARTMENT OF PUBLIC WORKS, DISTRICT OFFICE, WORCESTER.**

Inspected: Dec. 11, 1945 - W.O. Lindquist

61-01

June 16, 1948. LOM
Repairs: 35' of dike & wood sheetpiling, backfilling with sandy clay
fill and riprap upstream side.

DESCRIPTION OF DAM

DISTRICT 3

Submitted by MULCAHY DONALD Dam No. 9-14-946-1
 Date 2-7-73 City/Town WORCESTER
 Name of Dam QUINSIGAMOND ROND DAM

1. Location: Topo Sheet No. 21 B

Provide 8 1/2" x 11" in clear copy of topo map with location of Dam clearly indicated.

2. Year built: _____ Year/s of subsequent repairs _____

3. Purpose of Dam: Water Supply _____ Recreational _____
 Irrigation _____ Other ☒

4. Drainage Area: 58.85 sq. mi. _____ acres

5. Normal Ponding Area: 20 ± acres; Ave. depth _____

Impoundment: _____ gals.; _____ acre ft.

6. No. and type of dwellings located adjacent to pond or reservoir
1 CAS STA
BUS BUILDING i.e. summer homes, etc. _____

7. Dimensions of Dam: Length 225' ± Max. Height 11'

Slopes: Upstream Face VERTICAL

Downstream Face VERTICAL

Width across top 50' ±

8. Classification of Dam by Material:

Earth ☒ Conc. Masonry _____ Stone Masonry ☒

Timber _____ Rockfill _____ Other _____

9. A. Description of present land usage downstream of dam:

_____ % rural; 100 % urban.

B. Is there a storage area or flood plain downstream of dam which could accommodate the impoundment in the event of a complete dam failure? yes ☒ no _____

DAM NO. 3-14-348-1

10. Risk to life and property in event of complete failure.

No. of people NONE.

No. of homes NONE.

No. of Businesses 1.

No. of industries 1. Type STEEL

No. of utilities NONE. Type _____

Railroads N.Y. N.H. RAILROAD.



Other dams NONE.

Other _____.

11. Attach Sketch of dam to this form showing section and plan on 8 1/2" x 11" sheet.

12. How to Locate: TRAVEL SOUTH ON MILLBURY ST FROM
INTERSECTION OF MILLBURY & BALLARD STS, DAM ON
RIGHT AT RAILROAD CROSSING.

WORLESTER
QUINSIGAMOND DAM
3-14-348-1



A-A SECTION

INSPECTION REPORT - DAMS AND RESERVOIRS

1. Location: City/Town WORCESTER Dam No. 3-14-348-1
 Name of Dam QUINSIGAMOND POND DAM Inspected by _____

Date of Inspection _____

2. Owner/s: per: Assessors _____ Prev. Inspection ☒

Reg. of Deeds _____ Pers. Contact _____

1. UNITED STATES STEEL CORP 767 MILLBURY ST WORCESTER
 Name St. & No. City/Town State Tel. No.

2. _____
 Name St. & No. City/Town State Tel. No.

3. _____
 Name St. & No. City/Town State Tel. No.

3. Caretaker (if any) e.g. superintendent, plant manager, appointed by absentee owner, appointed by multi owners.

Name: St. & No.:

City/Town: State: Tel. No.:

4. No. of Pictures taken NONE

5. Degree of Hazard: (if dam should fail completely)*

1. Minor _____ 2. Moderate ☒

3. Severe _____ 4. Disastrous _____

* This rating may change as land use changes (future development)

6. Outlet Controls: Automatic _____ Manual ☒

Operative _____ yes; _____ No.

Comments:

7. Upstream Face of Dam: Conditions:

1. Good _____ 2. Minor Repairs ☒

3. Major Repairs _____ 4. Urgent Repairs _____

or Comments:

8. Downstream Face of Dam:

Condition: 1. Good _____ 2. Minor Repairs ✓
 3. Major Repairs _____ 4. Urgent Repairs _____

Comments:

9. Emergency Spillway: NONE

Condition: 1. Good _____ 2. Minor Repairs _____
 3. Major Repairs _____ 4. Urgent Repairs _____

Comments:

10. Water Level at time of inspection: 3 ft. above _____ below ✓
 top of dam ✓ principal spillway _____
 other _____

11. Summary of Deficiencies Noted:

Growth (Trees and Brush) on Embankment ✓
 Animal Burrows and Washouts _____
 Damage to slopes or top of dam FALLEN TREE ON LEFT SIDE OF DAM
 Cracked or Damaged Masonry NONE VISIBLE
 Evidence of Seepage NONE
 Evidence of Piping NONE
 Erosion NONE
 Leaks NONE
 Trash and/or debris impeding flow TRASH & DEBRIS IN STREAM
 Clogged or blocked spillway TRASH AND DEBRIS BLOCKING SPILLWAY
 Other _____

12. Remarks & Recommendations: (Fully Explain)

THE STONE MASONRY SECTION OF THE DAM APPEARS TO BE IN GOOD CONDITION. THE PRIMARY DEFICIENCY IN THIS DAM IS THE AMOUNT OF TRASH AND DEBRIS LAYING ON TOP OF THE SPILLWAY FOR ALMOST HALF THE LENGTH OF THE SPILLWAY, WEEDS & HUMMOCKS GROWING IN APPROACH TO SPILLWAY COLLECT TRASH AND INHIBIT THE FLOW OF WATER, THERE IS AN UPROOTED TREE IN THE EXTREME LEFT SIDE OF THE DAM THAT IS LAYING IN THE POND ABOUT 25 FEET FROM THE TOP OF THE SPILLWAY. REMOVAL OF THIS TREE IS NECESSARY TO PREVENT LOSS OF SECTION TO EARTH DAM AND POSSIBLE TO DAMAGE TO GRANITE MASONRY WALL, AND ALSO DAMAGE TO SPILLWAY AND DOWNSTREAM SECTION OF DAM IF THE TREE SHOULD BE SWEEP OVER THE DAM.

A 20' SECTION OF THE WOODEN FLASHBOARDS AT THE EXTREME RIGHT SIDE OF SPILLWAY HAS BEEN TIPPED FORWARD AND A GREATER VOLUME OF WATER IS FLOWING THROUGH THIS SECTION OF THE DAM.

THE CONDITIONS LISTED SHOULD ALL BE CORRECTED TO INSURE PROPER FUNCTIONING OF THE DAM AND TO PREVENT POSSIBLE FUTURE DAMAGE TO THE STRUCTURE.


13. Overall Conditions:

1. Safe ✓
 2. Minor repairs needed ✓
 3. Conditionally safe - major repairs needed _____
 4. Unsafe _____
 5. Reservoir impoundment no longer exists (explain)
- Recommend removal from inspection list _____

APPENDIX C
PHOTOGRAPHS



**NO. 1 VIEW OF DAM CREST AND RAILROAD
BRIDGE FROM NORTH ABUTMENT**



**NO. 2 VIEW OF SOUTH ABUTMENT
SHOWING ABANDONED INTAKE STRUCTURE**



**NO. 3 VIEW OF GREENWOOD STREET BRIDGE
DOWNSTREAM FROM DAM**



**NO. 4 VIEW OF DOWNSTREAM CHANNEL FROM
GREENWOOD STREET BRIDGE**

APPENDIX D
HYDROLOGIC AND HYDRAULIC COMPUTATIONS

	<u>Page</u>
Figure D-1, Watershed Plan	in pocket
Hydrologic and Hydraulic Computations	D-2

TRUE NORTH

1. 2. 3. 4. 5. 6.


.....


100


Figure 1. The effect of the concentration of the *Agaricus bisporus* spores on the growth of *Agaricus bisporus* on the substrate. The concentration of the spores was 10⁴ (a), 10⁵ (b), 10⁶ (c), 10⁷ (d), 10⁸ (e) and 10⁹ (f) spores/g substrate. The substrate was composed of 100 g of straw and 100 g of manure. The substrate was incubated at 25 °C for 7 days. The substrate was then inoculated with the spores and incubated at 25 °C for 7 days. The substrate was then incubated at 25 °C for 7 days. The substrate was then incubated at 25 °C for 7 days.

400

177







MILLBURY

TO MILLBURY

30 34

30 35

517

30 36

30 37

30 38

30 39

30 40

30 41

30 42

30 43

30 44

30 45

30 46

30 47

30 48

30 49

30 50

30 51

30 52

30 53

30 54

30 55

30 56

30 57

30 58

30 59

30 60

30 61

30 62

30 63

30 64

30 65

30 66

30 67

30 68

30 69

30 70

30 71

30 72

30 73

30 74

30 75

30 76

30 77

30 78

30 79

30 80

30 81

30 82

30 83

30 84

30 85

30 86

30 87

30 88

30 89

30 90

30 91

30 92

30 93

30 94

30 95

30 96

30 97

30 98

30 99

30 100

30 101

30 102

30 103

30 104

30 105

30 106

30 107

30 108

30 109

30 110

30 111

30 112

30 113

30 114

30 115

30 116

30 117

30 118

30 119

30 120

30 121

30 122

30 123

30 124

30 125

30 126

30 127

30 128

30 129

30 130

30 131

30 132

30 133

30 134

30 135

30 136

30 137

30 138

30 139

30 140

30 141

30 142

30 143

30 144

30 145

30 146

30 147

30 148

30 149

30 150

30 151

30 152

30 153

30 154

30 155

30 156

30 157

30 158

30 159

30 160

30 161

30 162

30 163

30 164

30 165

30 166

30 167

30 168

30 169

30 170

30 171

30 172

30 173

30 174

30 175

30 176

30 177

30 178

30 179

30 180

30 181

30 182

30 183

30 184

30 185

30 186

30 187

30 188

30 189

30 190

30 191

30 192

30 193

30 194

30 195

30 196

30 197

30 198

30 199

30 200

30 201

30 202

30 203

30 204

30 205

30 206

30 207

30 208

30 209

30 210

30 211

30 212

30 213

30 214

30 215

30 216

30 217

30 218

30 219

30 220

30 221

30 222

30 223

30 224

30 225

30 226

30 227

30 228

30 229

30 230

30 231

30 232

30 233

30 234

30 235

30 236

30 237

30 238

30 239

30 240

30 241

30 242

30 243

30 244

30 245

30 246

30 247

30 248

30 249

30 250

30 251

30 252

30 253

30 254

30 255

30 256

30 257

30 258

30 259

30 260

30 261

30 262

30 263

30 264

30 265

30 266

30 267

30 268

30 269

30 270

30 271

30 272

30 273

30 274

30 275

30 276

30 277

30 278

30 279

30 280

30 281

30 282

30 283

30 284

30 285

30 286

30 287

30 288

30 289

30 290

30 291

30 292

30 293

30 294

30 295

30 296

30 297

30 298

30 299

30 300

30 301

30 302

30 303

30 304

30 305

30 306

30 307

30 308

30 309

30 310

30 311

30 312

30 313

30 314

30 315

30 316

30 317

30 318

30 319

30 320

30 321

30 322

30 323

30 324

30 325

30 326

30 327

30 328

30 329

30 330

30 331

30 332

30 333

30 334

30 335

30 336

30 337

30 338

30 339

30 340

30 341

30 342

30 343

30 344

30 345

30 346

30 347

30 348

30 349

30 350

30 351

30 352

30 353

30 354

30 355

30 356

30 357

30 358

30 359

30 360

30 361

30 362

30 363

30 364


30 365

30 366

3

COUNTY COMMISSIONER
JAN 1, 1947

MEETING DOCKET



SCALE IN MILES

WORCESTER COUNTY COMMISSIONERS
 WORCESTER COUNTY ENGINEERING DEPARTMENT
 PLAN OF
 DAMS
 FOR
 AMERICAN STEEL & WIRE CO.


COUNTY COMMISSIONERS

4

POND NAME		CAPACITY OF POND IN MILLIONS OF GAL	AREA OF POND IN ACRES	INDIVIDUAL WATERSHED IN ACRES	TOTAL WATERSHED IN ACRES	ELEV. OF TOP OF DAM SPILLWAY	ELEV. OF TOP OF FLASHBOSS TO SPEN- CER PAXTON CEN	PAXTON YEAR BUILT	ORIGINAL PR DAM	
61-02	CENTRAL WORKS *	5.3	5.3			443.40		1814		I
61-08	COES RESERVOIR *		119		4229					
61-05	CURTIS POND *	160	62	883	16663					
03-03	HILTON POND	40	26.4	1247	6732	96.56	98.38			I
61-15	LEESVILL POND	125		1522	15780					
03-05	MOSS RESERVOIR	256	158	699	699	110.79	112.17	CONCRETE	1921	I
03-04	PONDVILLE POND	125	45	2639	4746					
30-21	RAMSHORN POND	720	145	1527	1527	22.0	24.0	PREVIOUS	TO 1831	I
30-21	RAMSHORN MEADOW POND	22	38	580	2107					I
61-03	STILL WATER POND *	35	30	605	24319					
03-01	STONEVILLE POND		45	4870	7466					
03-02	STONEVILLE RESERVOIR	185	68	1772	1772					
03-07	SOUTHGATE POND	1.5	1.5	83	782					
61-01	SOUTH WORKS POND *	20.0	13.0	381	24700	438.04	440.04			I

* RUN OFF FROM WATERSHED EFFECTED BY CITY STREETS AND STORM SEWERS PLAN

NOTE: THE INFORMATION SHOWN ON THIS PLAN WAS DRAWN EXISTING PLANS, & PARTICULARLY THE G.E. GOODRICH REPORT NOV. 14, 1921 AND MOSS RESER



PAXTON

YEAR BUILT

TYPE OF DAM

ORIGINAL DAM PRESENT DAM

HIGH WATER MARK

1814 1899 EARTH MASONARY TIMBER CORE PLAN B 177 1899
REPAIRS 1936 PLAN 12718

ELEV 443.47 COPPER BOL
SOUTH OF AND 153' W FROM
3046 - BOUND IS SHOWN AS
WAY. PROP. PLAN - 8038

1232 GATE IS SCREW STEM 24" PIPE
EARTH WITH CONCRETE CORE WALL PLAN FOR CORE -
WALL 9042 - CONCRETE SPILLWAY PLAN 13530 - 31
10591 REPAIRS

ELEV. 473.51, TWO FEET BEL
OF SPILLWAY. WORCESTER
WATER RIGHTS PURCHASE
PAGE 293
PROPERTY PLAN 8034

CONCRETE EARTH ADDED

1921 1928 CONCRETE GRAVITY SECTION, COVERED WITH EARTH
GATE SCREW STEM, 30" x 30" BOX OUTLET

ELEV. 112.05 BRASS PLUG IN
SOUTH OF SPILLWAY CREST P
8044 A FOR PARCIS PURC

STONE MASONARY

PREVIOUS TO 1831 1872-3 GATE SCREW STEM, 24" x OUTLET PIPE (POSSIBLY) 30"
EARTH PUDDLED 10' EITHER SIDE CHESTNUT CUTOFF
WALL ALONG DAM & (1873) PLAN 13515 A & B

ELEV. 24.29 IRON PIN IN LEDGE
OF N.W. COR. OF N.W. BRIDGE

1916 GATE 36" x OUTLET
EARTH WITH CONCRETE CORE WALL, CONCRETE
SPILLWAY PLAN 7171

PROPERTY MAP 8033

RACK, PINON ?
CONCRETE ?

PROPERTY MAP 8769 (19

PROPERTY MAP 8769 (190

GATE 30" x OUTLET
EARTH & STONE WALL

FROM M. BONZEY 1917 BK. 21

1821 FLOOD GATE - RACK & PINION, INTAKE GATE - SCREW
STEM INSTALLED IN 1943 - MASONARY. PLAN 3955
INTAKE 14454 A-H SECTIONS THU. POND 3265
(1906) 12792 (1936)

ELEV. 443.47 SAME AS CE
ESTABLISHED IN EXCHANGE
CROSS, AM. S. & W. CO. CIT
P.F. & F.W. TAYLOR PROP.

PLANS FOR MOSS RES. DAM: CONCRETE, ORIGINAL DAM 8510 TO 12, PREG CONST. 10584, 10582-
PROPERTY, 1877, 8044A & LOTS PURCHASED IN CEDAR SWAMP 8771

NS, & FROM FILES OF SUPT. OF ENG. & MAINT.

RESERVOIR, DATA CONCERNING ORIGINAL OWNERS OF CEDAR SWAMP

LEICESTER

SCALE IN MILES

ER MARK & WATER RIGHTS

YEAR ESTABLISHED

UPPER BOLT TOP OF STONE BOUND 11.5
33' W FROM S.E. COR OF MILL FROM PLAN
S SHOWN AS 60' UP STREAM FROM SPILL -
AN - 8038

1873 BY SUPERIOR COURT DEGREE VOL 22
P 127. WASHBURN MOEN MFG. CO. VERSUS
CROMPTON CARPET CO DEFENDANT

AMERICAN

0 FEET BELOW BOLT IN EAST CONCRETE WALL
RCESTER ELECTRIC LIGHT PLAN 1336
PURCHASED 1917 FROM HILTON HEIRS BK 2123

JAN 30, 1914 BY H.A. PRATT PRIV. ENG

NO AGRE

NEW ENG
AM S & V
IN EMER

N 8034 HIGH WATER MARK

AMERICAN

CONSOLID

PLUG IN LEDGE, EAST SIDE OF POND, 208'
Y CREST PLANS 14628 - SEE PLAN
CHLS PURCHASE - ALSO 8771 - 8777

OCT. 21, 1924 BY COUNTY COMM.

AMERICAN

LAREE F
WE HAVE

N IN LEDGE ON WESTERLY SHORE ELEV.
W. BRIDGE WING WALL - 30.00

1872 REG. OF DEEDS, BK. 875, P132-149
PURCHASED BY A. CURTIS AS TRUSTEE FOR
RAMSHORN POND CO. PREVIOUS TO RAISING DAM

RAMSHORN
WORC CO
CO. CONS
EL ON BL
(AM S & V
(W. WIND

8033

WHITTAL
CALL EN

769 (1904)

(QUEENS
NEW EN
PURCHA

69 (1904)

7 BK. 2123, P.290

AMERICAN


(AS CENTRAL WORKS)
CHANGE OF TITLES BETWEEN HOLY
CO. CITY OF WORCESTER AND
PROP. PLAN 8041.

AP. 29, 1909 BK. 1904, P. 68 THIS IS
(TAYLOR DEED)

AMERICAN

10562-3, 10507 & S10400, S14628
8771

THIS DRAWING AND ALL INFORMATION T
AND IS CONFIDENTIAL AND MUST NOT B
AND IS SUBJECT TO RETURN UPON DEM

	FLOW CONTROLLED BY	MISC. INFORMATION
ESTABLISHED SUPERIOR COURT DEGREE VOL. 22 TURN MOEN MFG. CO. VERSUS PET CO. DEFENDANT	AMERICAN STEEL & WIRE CO. NO AGREEMENT - COES CO	
BY H.A. PRATT PRIV. ENG.	NEW ENG POWER ASSOCIATES AM S & W CO. CAN OBTAIN WATER IN EMERG. AMERICAN STEEL & WIRE CO.	OLDEST WATER PRIVILEGE IN ELEC. LIGHT CO. USES 2 MIL. GAL. FOR CONDENSING, POND KEPT
	CONSOLIDATED RENDERING CO.	NECESSARY TO KEEP POND FULL OF THEIR PUMPS.
BY COUNTY COMM.	AMERICAN STEEL & WIRE CO. LAREE FABRICS MILLS INC. WE HAVE NO AGREEMENT	DURING SUMMER MONTHS RES. OF WATER WITHOUT DRAW D. USED FOR CLEANING & CONDENSING NO POWER USE
REEDS, BK. 875, P. 132-149 A. CURTIS AS TRUSTEE FOR ID CO. PREVIOUS TO RAISING DAM	RAMSHORN POND ASS. - A. S. & W. CO. WORC. COUNTY ELEC. HOPEVILLE MFG. CO. CONSOL. RENDERING WHITTALL EL. ON BLACKSTONE RIVER (AM S & W. CO. DAY CLOVER, W. WINDLE WHITTALL ASSOCIATES CALL ENG. RM FOR FLASH BD. CHANGE	MIN. FLOW REQ. BY SMALL MILLS WEIR - 2,500,000 GAL. DAY FROM 1939 NEVER HAS EXCEEDED 10 USED FOR INFLOODING DURING RA. IN WINTER TO ENABLE CLOSING OF HORN POND GATE USED FOR POWER WHEN PLENTY WATER OTHER USE IS FOR CLEAN
	QUEENSBURY COMBING CO. NEW ENGLAND POWER ASSOCIATES PURCHASED IN 1945	THE AGREEMENT IS THAT QUEENSBURY COMBING CO. CAN DRAW SUFFICIENT WATER TO RUN PLANT WE CAN O. WATER BY CONSULTING N.E. FLOW
	AMERICAN STEEL & WIRE CO.	DAM WASHED OUT
K, 1904, P. 68 THIS IS	AMERICAN STEEL & WIRE CO.	18,700,000 GAL. PER DAY REQ. FOR SOUTH WORKS & WIRE MILL AS MEASURED IN 1942 PREPARING TO INTAKE CHANGES

THIS DRAWING AND ALL INFORMATION THEREON IS THE PROPERTY OF THE AMERICAN STEEL & WIRE CO. AND IS CONFIDENTIAL AND MUST NOT BE MADE PUBLIC OR COPIED UNLESS AUTHORIZED BY THEM AND IS SUBJECT TO RETURN UPON DEMAND.

AMERICAN STEEL & WIRE CO

COUNTY COMMISSIONERS

JAN 1, 1947

MEETING DOCKET

SCALES AS NOTED

TRAINING CHECKED BY

W.C.

DAM NO.

BY MISC. INFORMATION

COUNTY ENGINEER

OLDEST WATER PRIVILEGE IN SYSTEM, WORC. COUNTY
ELEC. LIGHT CO USES 2 MIL. GAL. 24 HRS (1921)
FOR CONDENSING, POND KEPT FULL

NECESSARY TO KEEP POND FULL FOR SUCTION
OF THEIR PUMPS

DURING SUMMER MONTHS RESERVOIR LOSES 2"
OF WATER WITHOUT DRAW DOWN

USED FOR CLEANING & CONDENSING PURPOSES
NO POWER USE

MIN. FLOW REQ BY SMALL MILLS WHEN IN OPERATION IS 6" THRU 36" WIRE
WEIR - 2,500,000 GAL. DAY FROM HW CLOVER, FLOW FROM 1904 TO
1939 NEVER HAS EXCEEDED 10" OVER SPILLWAY

USED FOR IMPONDING DURING RAINS &
IN WINTER TO ENABLE CLOSING OF RAMS
(HORN POND GATE)

USED FOR POWER WHEN PLENTY OF
WATER OTHER USE IS FOR CLEANING

(THE AGREEMENT IS THAT QUEENSBURY
COMBING CO CAN DRAW SUFFICIENT
WATER TO RUN PLANT, WE CAN OBTAIN
WATER BY CONSULTING N.E. POWER CO)

DAM WASHED OUT

18,700,000 GAL. PER DAY REG.
FOR SOUTH WORKS & WIRE MILL
AS MEASURED IN 1942 PREPARATORY
TO INTAKE CHANGES

PROPERTY OF THE AMERICAN STEEL & WIRE COMPANY
UNLESS AUTHORIZED BY THEM

AMERICAN STEEL & WIRE CO
SUBSIDIARY OF
UNITED STATES STEEL CORPORATION

ENGINEERING
DEPARTMENT

WORCESTER
MASS

U.S.S.

DRAWN BY JAN. 1, 1947, BROUGHT
SCALE 1" = 1/2 MILE

17720

WATER SHED OF
SOUTHWORKS POND

WATERSHED PLAN

Project Nat. Review of Non Fed. Dams Acct No 5864 Page 1 of 6
 Subject Worcester, Mass. Area Comptd By LEB Date 7/26/78
 Detail QUINSIGAMOND RES. DAM Chkd By PJR Date 3/1/79

(I) Peak Inflow Test Flood & 100 Year Flood & Storage Functions

A- Inflow Test Flood

Use "Leesville" Curve, adjusted by reduction factors due to area exceeding 10 mi²

Drain Area = 51.7 mi², P.F.R. (Leesville) = 850 cfs./mi²

[Ref. Fig 16 - "Design of Small Dams" - U.S. B.R. for Zone I]

Leesville - 32.1 mi² - reduction factor = 88%

Quinsigamon - 51.7 mi² - " " = 82%

Due to low dam use 50% of final value

Remove 6000 cfs diversion from final value

$$Q_A = \frac{1}{2}(850)(51.7) \cdot \frac{.82}{.88} - 6000 = 14,475 \text{ cfs} = Q_A$$

Alternate Method for Verification (prev. report values)

Peak Coes outflow - 10.9 mi² - Max Q = 8500

" Leesville " - 32.1 " " = 8700

* Remaining 8.7 sq mi - 8.7 " " = 2600

$$\frac{51.7}{11.3} \cdot 19800 \text{ cfs} = Q_B$$

* This Value = 2x Millbrook Drain Cap. x $\frac{8.7 \text{ mi}^2}{11.3}$
 with Millbrook taken at 1675 cfs from
 M & E Report & Factor of 2 for overland
 flow under extreme storm conditions

$$\text{Ave } Q_A \& Q_B \text{ for Inflow Test Flood} = 17140 \text{ cfs} \quad (331.5 \text{ c.s.m.})$$

B - 100 Year Test Flood (use prev. report values)

100 yr disch. from Coes - 3080

" " - Leesville - 234

Remaining Area: $1.2 \times 1675 \times \frac{8.7}{11.3} = 1547$

$$4860 \text{ cfs} = 100 \text{ Year St Inflow}$$

(94.0 c.s.m.)

C - Storage Functions

1- Inflow Test Flood.

$$Q_{\text{Final}} = Q_{\text{in}} \left(1 - \frac{S_{\text{Final}}}{9.5''}\right); F_{TF} = 17140 - 1804 \text{ S}$$

$$2- 100 \text{ yr. Flood: } F_{100} = 4860 - 1034 \text{ S}$$

$$S = \text{inches on watershed equal to reservoir stor.} = 12 D \cdot \frac{.02}{51.7} = .00464 D$$

where D is Storage Depth on Reservoir in feet


METCALF & EDDY, ENGINEERS

Project Nat. Review of Non Fed. Dams Acct No. 5864 Page 2 of 6
 Subject Worcester Mass Area Comptd By LEB Date 7/26/78
 Detail QUINSIGAMOND RES. DAM Ck'd By RW Date 8/7/78

II Discharge & Storage Function vs Pond Elev.

A- Weir

Narrow stone weir. Silt level to top of weir along most of its length. Assume high flood flows will erode 2' of silt behind weir. Length of weir 152.2' (use chord length)



$$C_w = 3.27 + 0.4 \frac{H_w}{h} \quad \text{in} \quad Q_w = C_w H_w^{3/2}$$

B- Crest (Overland) Flow

Assume no sizeable "Crest" flow until pond reaches elev. 447.5. This is due to R.E. tracks just downstream.

Use 270' length for crest flow up to elevation 450

Based on broad crested weir relation:

$$Q_c = 2.55 (H_c)^{3/2} ; H_c = H_w - 6.5 ; Q_c = 688.5 H_c^{1.5}$$

C- Totals

METCALF & EDDY, ENGINEERS

Pond Elev	H _w	C _w	Q _w	Q _c	Q _{Tot}	S	F _{TF}	F ₁₀₀
			L=152.2					
442	1	3.47	3.47	528	—	528		
443	2	3.67	10.38	1580	—	1580		
444	3	3.87	20.11	3060	—	3060	.014	4846
445	4	4.07	32.56	4956	—	4956	.018	4840
446	5	4.27	47.74	7267	—	7267	.023	
447	6	4.47	65.70	10000	—	10000		
448	7	4.67	86.5	13165	243	13400	.032	17081
449	8	4.87	110.2	16772	1265	18000	.037	17073
450	9	5.07	136.9	20836	2721	23600	.042	

Project
Subject
Detail

Acct. No. 5864


Comptd. By LEB

Ck'd. By RW

Page 3 of 6

Date 7/26/78

Date 8/7/76



Discharge in c.f.s.

Project Nat Review of Non Fed Dams Acct. No 5864 Page 4 of 6
 Subject Worcester Mass. Area Comptd By LJB Date 7/27/78
 Detail QUINSIGAMOND RESERVOIR DAM Ckd. By RW Date 3/7/79

IV Failure of Dam - A-Failure with Pond @ Weir Elev.

Peak Failure Flow:

Pond Elevation - 445.7

Toe Elevation - 433.0 ±

$Y_0 = 12.7$

Dam Length Subject to Breaching = 152' (Mainly Spillway)

$W_0 = 40\% (152) = 61'$

$$Q_P = 1.68 W_0 (Y_0)^{1.5} = 1.68 (61') (12.7)^{1.5} = 4640 \text{ c.f.s.}$$

Spillway Disch. 6600 cfs; T.W. Depth 5.5', Area = 1004 ft²; $Q_1 = 11240$ cfs

Storage Volume Released:

Storage Above Spillway: From Graph = 83

Storage Below Spillway: $2 (.02) 640 = 26$


$S = \text{Total Storage} = 109 \text{ acre ft.}$

Channel Hydraulics:


$$S = \frac{10}{1800} = .00555; n = .04$$

$$A = y(100 + 15y); P \approx B = 100 + 30y$$

$$V = 2.78 R^{4/3}$$



y	A	P	$R^{4/3}$	V	Q
2	260	160	1.382	3.84	999
4	640	220	2.038	5.67	3626
6	1140	280	2.550	7.09	8081
8	1760	340	2.990	8.32	14641
10	2500	400	3.393	9.43	23582
12	3360	460	4.433	12.32	41407



1st Reach: 400' to bldg. @ channel bend

$$Q_1 = 11240; y_1 = 7.1'; A_1 = 1466; \Delta Vol_1 = 4.2 \text{ ac ft.}$$

$$Q_2 = 11240 \left(1 - \frac{4.2}{109}\right) = 10800 \text{ cfs. ; Wave Ht. } \approx 7.0'$$


$$\text{Say } Q_{\text{final}} = 11000 \text{ cfs. , } y \approx 7.0', \Delta TW = 1.5'$$

Time to Drain:

$$\frac{43560 (109)}{3600 (\frac{1}{2}) (4640)} = 0.57 \text{ Hours. } = 34 \text{ Min.}$$

Project Nat. Review of Non Fed Dams Acct. No. 5864 Page 5 of 6
 Subject Worcester Mass. Area Comptd By LEB Date 8/25/78
 Detail QUINSIGAMOND RESERVOIR DAM Ck'd. By _____ Date _____

IV Failure of Dam (cont.)



B - Failure Under Peak Flow:

The only major section of this dam likely to fail under high flows is the 152' of weir section.

Prior to failure at peak flows this section disch. at 105.2 cfs/ft

The failure of a section of the weir would result in a discharge of:

$$Y_0 = 448.8 - 441.7 = 7.1'; q_p = 1.68(7.1)^{1.5} = 31.8 \text{ cfs/ft}$$

Total Failure Flow:

$$Q_T = 17075 + 61(31.8) = 19000 \text{ cfs}$$

Tailwater would rise from 8.7' depth to 9.0' depth due to dam failure during peak Test Flood outflow

Project Nat. Review of Non Fed. Dams Acct. No 5864 Page 6 of 6
 Subject Worcester Mass Area Comptd By LEB Date 7/27/78
 Detail QUINSIGAMOND RES. DAM Ckd. By BW Date 8/2/78

(V) Summary of Resulting Flows

A. Inflow Test Flood

Peak Outflow 17075 c.f.s. @ Pond El. 448.8 (330 csm)

Peak Spillway Flow = 16055 cfs

Peak Overland (Crest) Flow = 1020 cfs.

Unit Overland Flow = $\frac{1020}{270} = 3.78 \text{ cfs/ft}$

Critical Depth = 0.76 ; Critical Vel. = 5.0 fpr.

Tailwater El. (approx.) = 8.0' + 433 = 441.0

B. 100 Year Flood

Peak Outflow 4845 c.f.s. @ Pond El. 444.9 (94 csm)

No Appreciable Overland (Crest) Flow

Tailwater Elev. (approx.) = 4.5' + 433 = 437.5

(VI) Outlet Capacity

Length is short - treat as orifice 4.75' x 3' wide

Inu El. 433.4 , Pond El. 441.0 , Head = 7.6' , $H/D = \frac{7.6}{4.75} = 1.6$

$Q = 3 \times 50 = 150 \text{ cfs. (2.9 c.s.m.) [With Pond @ Dam Crest El.]}$

APPENDIX E
INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

INVENTORY OF DAMS IN THE UNITED STATES

IDENTITY NUMBER	STATE	COUNTY	CORNER	NAME	LATITUDE (NORTH)	LONGITUDE (WEST)	REPORT DATE DAY MO YR
MA 159 NED	MA	027 03		QUINSIGAMOND POND DAM	42 14.1	71 47.6	06 SEP 78

POPULAR NAME	NAME OF IMPROVEMENT
	QUINSIGAMOND POND

RECORDS	RIVER OR STREAM	NEAREST DOWNSTREAM CITY-TOWN-VILLAGE	DIST FROM DAM (MI.)	POPULATION
01 06	BLACKSTONE RIVER	Worcester	0	172300

TYPE OF DAM	YEAR COMPLETED	PURPOSES	HYDRAULIC HEIGHT (FT)	IMPOUNDING CAPACITIES (ACRE-FT)	REGULATORY AGENCY
REGNPS	1891	R	18	180	100

DIST OWN FED R PRV/FED SCS A VER/DATE
N N N N N 8 SEP 78

REMARKS

D/S HAS	SPILLWAY	MAXIMUM DISCHARGE (CFS)	VOLUME OF DAM (CU YD)	POWER CAPACITY (MW)	INSTALLED PROPOSED NO	LENGTH (FT)	WIDTH (FT)	HEIGHT (FT)	WEIR LENGTH (FT)
1	240 U 155	400	2100						

OWNER	ENGINEERING BY	CONSTRUCTION BY
WILEY STOKES COMPANY	J W ELLIS	UNKNOWN

DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE
NONE	NONE	NONE	NONE

INSPECTION BY	INSPECTION DATE DAY MO YR	AUTHORITY FOR INSPECTION
WETCALF + EDDY, INC.	03 AUG 78	PUBLIC LAW 92-367

REMARKS